

GOVERNMENT OF ANDHRA PRADESH
A B S T R A C T

NREGS – AP and Other developmental schemes – Revision of Rural Standard Schedule of rates (RSSR) – Orders – Issued.

PANCHAYAT RAJ AND RURAL DEVELOPMENT (RD.II) DEPARTMENT

G.O.Ms.No.195

Dated:29.06.2009

Read the following:

1. G.O.Ms.No.65, PR&RD (RD.II) Dept., dated:06.03.2007
2. G.O.Ms.No.146, PR&RD (RD.II) Dept., dated:24-04-2007
3. Govt. Memo No.8299/RD.II/A1/2009-1, dated:21-05-2009

ORDER :

In the reference 2nd read above, Government issued orders on Rural Standard Schedule of Rates (RSSR) for unskilled manual task in works taken up under NREGS.

2. During the peak season of execution of works several Project Directors, DWMA reported that rates are not workable for certain tasks like removal of stumps , etc.

3. In the reference 3rd read above, Government issued orders revising the minimum wage for unskilled manual work taken up under NREGS from Rs.80/- to Rs.100/-.

4. In view of the above and in partial modification of G.O.Ms.No. 146 PR&RD (RD.II) Department dt.2.4.2007, Government orders revision of rates for manual tasks in RSSR, work wise, task wise rates are annexed to this order.

5. These orders shall come into effect immediately.

6. The copy of the GO is available on website www.rd.ap.gov.in

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

K.RAJU

Principal Secretary to Government (R.D.)

To

The Commissioner, Rural Development, AP., Hyderabad

The Director (EGS) O/o the Commissioner (RD)

All the District Collectors and District Programme Coordinators, NREGS

All the Project Directors, DWMA & Addl. District Programme Coordinators, NREGS

All the Project Directors, DRDAs and Additional District Programme Coordinators, NREGS

All the Chief Executive Officers, ZPs and Additional District Programme Coordinators, NREGS.

The Project Officer, ITDA and Additional District Programme Coordinators of Eturu Nagaram (Warangal), Bhadrachalam (Khammam), Utnoor (Adilabad) and Parvathipuram (Vizianagaram), Srisailam (Kurnool), Paderu (Visakhapatnam), Seethampeta (Srikakulam), Rampachodavaram (East Godavari) & KR Puram (West Godavari)

Copy to:

The Prl. Secretary, Finance (W&P) Dept., Govt. of A.P., Hyderabad.

The Prl. Secretary, PR., Govt. of A.P., Hyderabad.

The Prl. Secretary, Irrigation (I&CAD) of A.P., Hyderabad.

The Prl. Secretary, Tribal Welfare Dept., Govt. of A.P., Hyderabad.

The Secretary, R&B, Govt. of A.P., Hyderabad

The Prl. Secretary, EFS & T Dept., Govt. of A.P., Hyderabad

The Prl. Chief Conservator of Forests, Govt. of AP., Hyderabad

The Commissioner Disaster Management and EO Secy. to Govt.

The Commissioner, AMR-APARD, Rajendranagar, Hyderabad
The Commissioner, Tribal Welfare, Hyderabad
The Chairman and Members of Technical Committee.
The Engineer-in-Chief, Panchayat Raj Dept.
The Engineer-in-Chief, Irrigation Dept.
The Chief Engineer, Tribal Welfare
The Special Officers of NREGS–AP Districts
The Secretary, APREG Council, Hyderabad.
The Superintending Engineers of Panchayat Raj of NREGS –AP Districts.
The Superintending Engineers of Irrigation Dept., of NREGS –AP Districts.
PS to Prl. Secretary, RD, Govt. of A.P., Hyderabad
PR&RD (Gent) Dept., (2 copies)
SF/SC.

//FORWARDED :: BY ORDER//

SECTION OFFICER

ANNEXURE to GO Ms.No.195, PR&RD (RD-II) (Department), dated :29 /06/2009

S. No.	Item of Work	Rate approved in RSSR (G.O.Ms. No.146 Dt 24. 04.2007 (in Rs.)	Rates enhanced in the month 0f Feb 2009 (in Rs.)	Rates now approved to ensure mini. Wage of Rs.100/- (in Rs.)	Remarks
01	Unskilled Labour	80 /- day	80/- per day	100/- per day	-
02	Bush clearance				
	i) Light shrub	1.5 / Sqm	2.00/sqm	2.5/sqm	
	ii) Medium and Dense Shrub /besharam/rubber plants	2.0 / Sqm	2.50/sqm	3.15/sqm	
	iii)Thin stemmed Julyflora (stem with periphery upto 150 cms)/ thick shrub	4.5 / Sqm	5.0 / Sqm	6.25/sqm	Thick shrub is relevant in tribal areas only
	iv)Thick stemmed Julyflora (stem with periphery more than 150 cms	-	-	9.35/Sqm	New item
03	Removal of stumps				
	i) Removal of stumps of girth 30cms to 99cms(small stumps)	22/per each	40/-per each	50/- per each	Earlier adopted from relevant CSSR
	ii) Removal of stumps of girth 100cms to 199cms(medium stumps)	30/per each	50/-per each	62.5/- per each	Earlier adopted from relevant CSSR
	iii) Removal of stumps of girth 200cms to 299 cms(large stumps)	42/per each	65/-per each	81.25/- per each	Earlier adopted from relevant CSSR
	iv) Removal of stumps of girth 300cms to 399 cms(large stumps)	-	85/-per each	106.25/- per each	New item
	v) Removal of stumps of girth 400cms to 499 cms(large stumps)	-	110/-per each	137.5/- per each	New item
	vi) Removal of stumps of girth 500cms to 599 cms(large stumps)	-	135/-per each	168.75/- per each	New item
	vii) Removal of stumps of girth 600cms to 699 cms(large stumps)	-	170/-per each	212.50/-per each	New item
	viii) Removal of stumps of girth 700cms to 799 cms(large stumps)	-	220/-per each	275/-per each	New item
	ix) Removal of stumps of girth 800cms to 899 cms(large stumps)	-	275/-per each	343.75/-per each	New item

04	Earth work Excavation in Ordinary Soils				
	Category-I				
	i) Roads, rock fill dams and desilting of tanks	47 / Cum	47/ Cum	58.75/ Cum	-
	ii. a) Earth work excavation for contour bunding	35.0 / Cum	35/ Cum	43.75/ Cum	-
	ii. b) Breaking of clods, tamping & sectioning for contour bunding	12.00 / Cum	12.00 / Cum	15.00 / Cum	-
	Category-II				
	i) Farm ponds	66.00 / Cum	80.00 / Cum	100.00 / Cum	-
	ii) Plantation pits				
	a) 0.9 mtsX0.9 mtsX0.9 mts size pit	68.00 / Cum	68.00 / Cum	85.00 / Cum	-
	b) 0.6 mts X 0.6 mtsX 0.6 mts size of pit	68.00 / Cum	68.00 / Cum	85.00 / Cum	-
	c) 0.45 mts X 0.45 mtsX 0.45 mts size of pit	60.00 / Cum	60.00 / Cum	75.00 / Cum	-
	d) 0.3 mts X 0.3 mtsX 0.3 mts size of pit	60.00 / Cum	60.00 / Cum	75.00 / Cum	-
	Category – III				
	All other works	54.00 / Cum	65.00 / Cum	81.15 / Cum	-
05	Earthwork Excavation in Hard soils				
	Category-I				
	i) Roads and rock fill dams	58.00 / Cum	58.00 / Cum	72.50/ Cum	-
	ii) a) Earth work Excavation for contour Bunding	44.00 / Cum	44.00 / Cum	55/ Cum	-
	ii) b) Breaking of clods, tamping and sectioning for contour bunding	14.00 / Cum	14.00 / Cum	17.50/ Cum	-
	Category-II				
	i) Farm ponds	86.00 / Cum	90.00 /cum	112.50/cum	-
	ii) Plantation pits				
	a) 0.9 mtsX0.9 mtsX0.9 mts size pit	77.0 / Cum	77/cum	96.25/cum	-
	b) 0.6 mts X 0.6 mtsX 0.6 mts size of pit	77.0 / Cum	77/cum	96.25/cum	-
	c) 0.45 mts X 0.45 mtsX 0.45 mts size of pit	68.0 / Cum	68/cum	85.00/cum	-

	d) 0.3 mts X 0.3 mtsX 0.3 mts size of pit	68.0 / Cum	68/cum	85.00/cum	-
	Category -III				
	All other works	59.0 / Cum	68/cum	85.00/cum	-
06	Earth work excavation in soils with mixture of gravel and soft disintegrated rock boulders (stoney earth)				
	Category-I				
	i) Roads and rock fill dams	-	-	80/ Cum	New Item
	ii) a) Earth work Excavation for contour Bunding	-	-	60/ Cum	New Item
	ii) b) Breaking of clods, tamping and sectioning for contour bunding	-	-	20/ Cum	New Item
	Category-II				
	i) Farm ponds	-	-	110 / cum	New Item
	ii) Plantation pits				
	a) 0.9 mtsX0.9 mtsX0.9 mts size pit	-	-	100 / cum	New Item
	b) 0.6 mts X 0.6 mtsX 0.6 mts size of pit	-	-	100/- cum	New Item
	c) 0.45 mts X 0.45 mtsX 0.45 mts size of pit	-	-	90/- cum	New Item
	d) 0.3 mts X 0.3 mtsX 0.3 mts size of pit	-	-	90/- cum	New Item
	Category – III				
	All other works	-	-	90/- cum	New item
07	Earthwork excavation in soft disintegrated rock soils				
	Category – II				
	Farm ponds	100.0 /cum	100/cum	125.00/cum	-
	Category – III				
	All other works	90.0 / cum	90/cum	112.50/cum	-
08	STONE PITCING (Unskilled)				
	i) Farm Ponds – Labour charges for pitching only.	135 / Cum	175/cum	218.75/cum	-
	ii) Minipercolation Tanks – Labour charges for ptiching only.	135 / Cum	175/cum	218.75/cum	-

09	Rough Stone Dry Packing (Unskilled)				
	i) Rock Fill Dam, Stone Checks & Stone outlets – Labour charges for packing only.	60 / Cum	100/cum	125.00/cum	-
	ii) Stone Terracing – Labour charges for packing only.	60 / Cum	100/cum	125.00/cum	-
10	Benching with 0.45mx 0.45m size and 0.60mx0.30m size	-	12/-Rmt	15/-Rmt	New item
11	Carrying of earth / gravel by head loads – Leads & Lifts				
	i).For every additional Lead of 10 mts over and above initial lead of 10mt	10/cum	10/cum	12.50/cum	-
	ii).For every additional lift of 1mt over and above initial lift of 2mts	10/Cum	10/cum	12.50/cum	-
12	Conveyance of silt , carted earth, stable casing soil and gravel excluding loading and unloading <u>(In case of MI Tank work only), with Lead of</u>				
	a) 0.25km	-	-	24/-cum	New item
	b)0.50km	-	-	30/- cum	New item
	c)1 km	-	-	36/- cum	New item
	d) 2 km	-	-	42/- cum	New item
	e) 3 km	-	-	48/- cum	New item
	f) 4km	-	-	54/-cum	New item
	g) 5km	-	-	64/-cum	New item
	h) 6km	-	-	72/-cum	New item
	i) 7 km	-	-	80/-cum	New item
	j) 8 km	-	-	88/-cum	New item
	k) 9 km	-	-	96/-cum	New item
	l) 10 km	-	-	104/-cum	New item
13	Sharpening of crowbar	20/ week(3/- per day)	5/- per day or 35/- per week	5/- per day	New item
14	Basket Replenishment charges	Rs 2/- per day	Rs 3/- per day	3/- per day	New item
15	Plantation works				
	Category : I				
	i) Survey and demarcation	13/100 Nos	13/- 100 Nos.	16.25/- 100 Nos	-
	ii) Alignment and fixing of planting point with 0.45 meters length sticks	37.50/100 Nos	37.5/- 100 Nos.	46.85/- 100 Nos.	-

	iii) 0.45 meter sticks preparation and transportation at site.	20/100 Nos	20/- 100 Nos.	25/- 100 Nos.	-
	iv) a) Internal transportation of bag plants to planting points. (5"x9")	20.00/100 Nos	20/- 100 Nos.	25/- 100 Nos.	-
	iv) b) Internal transportation of Avenue Plantation. Tall plants	77.60/100 Nos.	77.60/- 100 Nos.	97/- 100 Nos.	-
	v) Refilling of Pits and planting (mXmXm), staking stick				
	a) 0.30 X 0.30 X 0.30 Size pit	0.50 / Each	0.50/- each	0.60/- each	-
	b) 0.45 X 0.45 X 0.45 Size pit	1.50 / Each	1.50/- each	1.85/- each	-
	c) 0.60 X 0.60 X 0.60 Size pit	3.00/ Each	3.00/- each	3.75/- each	-
	d) 0.90 X 0.90 X 0.90 Size pit	4.50 Each	4.50/- each	5.60/- each	-
	e) 1.00 X 1.00 X 1.00 Size pit	5.00 / Each	5.00/- each	6.25/- each	-
	Soil working and weeding				
	Category : I (1 M dia and 0.1 m Depth)				
	1) Avenue Plantation	5 / Each	5/- each	6.25/- each	-
	2) Horticulture	5 / Each	5/- each	6.25/- each	-
	Category : II (0.5 M dia and 0.1 m Depth)				
	i) Fore shore plantation	1.5 / Each	1.5/- each	1.85/- each	-
	ii) B.H.Afforestation	1.5 / Each	1.5/- each	1.85/- each	-
	iii) Bio Diesel Plantation & Block plantation	1.5 / Each	1.5/- each	1.85/- each	-
16	Causality Replacement for				
	i) Reopening of Pits for avenue, Horticulture & Blok Plantations.	5.1 / each	5.1/- each	6.35/- each	-
	ii) Fore share plantation, Barren Hill Afforestation, Bio-Diesel	2.5 / each	2.50/- each	3.10/- each	-
17	Watch & Ward and repair to Fence and soil working of each plant including pruning of branches for plantations raised in common property resource lands and lands of SC/ST/assignees.	80/day	80/- day	100/- day	-

18	Bio Fencing / Brush Wood Fencing for barren hill afforestation.				
	i) Nurseries, block plantation and fore shore plantation including collection, transportation and fixing at site	10 / Rmt	10/- Rmt	12.5/- Rmt	-
	ii) Avenue Plantation including collection, transportation and fixing at site (Size of 1 m dia and 1.5 m height)	37.85 / each	37.85/- each	47.30/- each	-
	iii) Horticulture, for lands of SC-ST & Assignee lands only	1000 /acre	1000/- acre	1250/- acre	-
	iv) Horticulture fencing 1 st year & 2 nd year maintenance SC-ST& Assignee lands only.	250/acre	250/- acre	312.50/- acre	-
19	Deep Ploughing in				
	i) Fallow Land and Hard Gravel soils (Depth not less than 0.3 meters) using ploughing tractors	1000 / acre	1000/- acre	1000/- acre	-
	ii) fallow land in ordinary soils using ploghing tractor depth not less than 0.3 m	800 / acre	800/- acre	800/- acre	-
	iii) Cattle cultivator(Double ploughing) in ordinary soils.	600 / acre	600/- acre	600/- acre	-
20	Watering plants of block plantation from the sump constructed (where ever one sump is available per one acre)	1.3 / plant	1.3/- plant	1.60/- plant	-
21	Watering plants from hand pump/bore well/open well up to distance of 30 mt	1.8 / plant	1.8/- plant	2.25/- plant	-
22	Watering block plantation from the nearby sources i.e bore well open well or kunta beyond 30 mts distance.	2.25 / plant	2.25/- plant	2.80/- plant	-
23	Hire charges of tractor mounted water tanker for filling sump	250 per one trip tanker of 5000 ltrs capacity	250/- per one trip of 5000 ltrs capacity	300/- per one trip of 5000 ltrs capacity	-

24	Construction of sump with 3 Nos of RCC Rings of 4 feet diameter , 1 foot height and 2 inch thickness prepared by using 2 Nos. of 4 mm dia MS rods with CM(1:5) and 4 mm dia metal chips for a sump with an inner volume of 37.68 cu.ft with 1066 litres capacity.	-	-	1200/- each sump	New specification is introduced
25	Labour charges for Spreading of silt unloaded by tractor in the field	9.75 / Cum	9.75/- cum	12.15/- cum	-
26	Labour charges for breaking clods, trimming, sectioning and manual compaction using Dimmisa	-	-	15.00/-cum	New item
27	Removal of water hycinth upto 30cms thick	-	-	3.75/Sqm	New item
28	Removal of water hycinth of more than 30cms thick	-	-	5.12/Sqm	New item

Note : Rates of all materials and conveyance rates of materials other than silt, carted earth, stable casing soil and gravel shall be adopted from the relevant CSSR.

K.RAJU
PRINCIPAL SECRETARY TO GOVERNMENT (RD)

SECTION OFFICER.